Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Stiff high strength orangish brown sandy CLAY. (WEATHERED BEE LOW LIMESTONE FORMATION)					S 3.00-3.45	(8) 15			PP 3.00	PP=85			
										PP 3.50	PP=92	3.50		D
						S 4.00-4.45	(10) 11			PP 4.00	PP=96			
										PP 4.50	PP=96	4.50		D
						S 5.00-5.45	(9) 16							
	BOREHOLE TERMINATED AT 5.45m	5.45	317.81											

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes

Backfilled with arisings. Combined gas and water monitoring standpipe installed.

Groundwater observations

No groundwater encountered.

Title

Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	90
1.00 - 2.00	70
2.00 - 3.00	100
3.00 - 4.00	100
4.00 - 5.00	90

Method Driven tube sampler	**Logged by** TO	**Date(s)** 31/01/2019
Level (m OD) 323.26	**Compiled by** SA	**Sheet number** Sheet 2 of 2
Co-ordinates 406827mE, 374235mN	**Checked by** SD	**DTS13**

Report ref: STQ4642M-G01 **Revision:** 0

Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Grass over dark brown slightly clayey SAND. (TOPSOIL)											0.30		D
	Stiff medium strength brown gravelly CLAY. Gravel consists of medium to coarse angular limestone. (WEATHERED EYAM LIMESTONE FORMATION)	0.50	313.89									0.50		D
										PP 0.80	PP=50	0.80		D
						S 1.00-1.45	(1) 2							
										PP 1.20	PP=50	1.20		D
	BOREHOLE TERMINATED AT 1.50m	1.50	312.89			C 1.50-1.52	(25 blows for 10mm penetration) then 50 blows for 10mm penetration							

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes

Backfilled with arisings. Borehole terminated due to competency of deposits (likely bedrock).

Groundwater observations

No groundwater encountered.

Title

Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	100
1.00 - 1.52	100

Method
Driven tube sampler

Logged by
TO

Date(s)
08/02/2019

Level (m OD)
314.39

Compiled by
SA

Sheet number
Sheet 1 of 1

Co-ordinates
406643mE, 374289mN

Checked by
SD

DTS15

Report ref: STQ4642M-G01

Revision: 0

Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Grass over dark brown clayey SAND. (MADE GROUND - REWORKED TOPSOIL)													
	Loose to medium dense dark brown mottled orangish brown dark grey slightly sandy GRAVEL. Gravel consists of fine angular slag, brick, coal and glass. (MADE GROUND)	0.30	323.96									0.30		D
												0.50		D
												0.80		D
						S 1.00-1.45	(4) 13			PP 1.00	PP=96			
												1.20		D
										PP 1.50	PP=100			
												1.80		D
						S 2.00-2.45	(1) 5			PP 2.00	PP=100			
										PP 2.50	PP=92	2.50		D
	CONTINUED ON NEXT SHEET													

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes
Backfilled with arisings.

Groundwater observations
No groundwater encountered.

Title
Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	80
1.00 - 2.00	90
2.00 - 3.00	90
3.00 - 4.00	50
4.00 - 5.00	30

Method
Driven tube sampler

Logged by
TO

Date(s)
31/01/2019

Level (m OD)
324.26

Compiled by
SA

Sheet number
Sheet 1 of 2

Co-ordinates
406749mE, 374220mN

Checked by
SD

DTS18

Report ref: STQ4642M-G01

Revision: 0

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Loose to medium dense dark brown mottled orangish brown dark grey slightly sandy GRAVEL. Gravel consists of fine angular slag, brick, coal and glass. (MADE GROUND)	3.00	321.26			S 3.00-3.45	(1) 2			PP 3.10	PP=0			
	Soft low strength orangish brown sandy CLAY. (POSSIBLE REWORKED WEATHERED BEE LOW LIMESTONE FORMATION)									PP 3.60	PP=0	3.50		D
						S 4.00-4.45	(0) 0			PP 4.10	PP=4			
										PP 4.70	PP=4	4.50		D
						S 5.00-5.45	(0) 0							
	BOREHOLE TERMINATED AT 5.45m	5.45	318.81											

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes

Backfilled with arisings.

Groundwater observations

No groundwater encountered.

Title

Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	80
1.00 - 2.00	90
2.00 - 3.00	90
3.00 - 4.00	50
4.00 - 5.00	30

Method
Driven tube sampler

Logged by
TO

Date(s)
31/01/2019

Level (m OD)
324.26

Compiled by
SA

Sheet number
Sheet 2 of 2

Co-ordinates
406749mE, 374220mN

Checked by
SD

DTS18

Report ref: STQ4642M-G01

Revision: 0

Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Grass over dark brown slightly clayey SAND. (TOPSOIL - MADE GROUND)													
	Stiff brown mottled grey very gravelly very sandy CLAY. Gravel consists of fine to medium angular limestone and sandstone. (MADE GROUND)	0.30	303.29									0.30		D
	Dark brown very clayey GRAVEL. Gravel consists of fine to medium angular shell, bricks, plastic, timber, slag and coal. (MADE GROUND)	0.50	303.09									0.50		D
												0.80		D
												1.20		D
												1.80		D
												2.50		D
	CONTINUED ON NEXT SHEET													

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes
Backfilled with arisings.

Groundwater observations
No groundwater encountered.

Title
Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	90
1.00 - 2.00	60
2.00 - 3.00	40
3.00 - 4.00	100

Method
Driven tube sampler

Logged by
TO

Date(s)
06/02/2019

Level (m OD)
303.59

Compiled by
SA

Sheet number
Sheet 1 of 2

Co-ordinates
406486mE, 374505mN

Checked by
SD

DTS27

Report ref: STQ4642M-G01

Revision: 0

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Dark brown very clayey GRAVEL. Gravel consists of fine to medium angular shell, bricks, plastic, timber, slag and coal. (MADE GROUND)											3.50		D
	BOREHOLE TERMINATED AT 4.00m	4.00	299.59											

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes
Backfilled with arisings.

Groundwater observations
No groundwater encountered.

Title
Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	90
1.00 - 2.00	60
2.00 - 3.00	40
3.00 - 4.00	100

Method
Driven tube sampler

Logged by
TO

Date(s)
06/02/2019

Level (m OD)
303.59

Compiled by
SA

Sheet number
Sheet 2 of 2

Co-ordinates
406486mE, 374505mN

Checked by
SD

DTS27

Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Vegetation over dark brown very clayey SAND. (TOPSOIL)													
	Stiff medium strength brown very sandy CLAY. (WEATHERED BOWLAND SHALE FORMATION)	0.30	299.13									0.30		D
												0.50		D
	Dark grey GRAVEL. Gravel consists of fine angular shale. (WEATHERED BOWLAND SHALE FORMATION)	0.80	298.63									0.80		D
												1.20		D
												1.50		D
	BOREHOLE TERMINATED AT 2.80m	2.80	296.63											

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes

Backfilled with arisings. Borehole terminated due to competency of deposits (likely bedrock).

Groundwater observations

No groundwater encountered.

Title

Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	95
1.00 - 1.50	100

Method
Driven tube sampler

Logged by
TO

Date(s)
06/02/2019

Level (m OD)
299.43

Compiled by
SA

Sheet number
Sheet 1 of 1

Co-ordinates
406514mE, 374343mN

Checked by
SD

DTS28

Report ref: STQ4642M-G01

Revision: 0

Proposed residential development
Nunsfield Road, Buxton

soiltechnics
environmental and geotechnical consultants

WELL	STRATA				WATER STRIKES	SPT TESTING				OTHER IN SITU TESTING		SAMPLING		
	DESCRIPTION	DEPTH (m)	REDUCED LVL (m OD)	LEGEND		TYPE / DEPTH (m)	RESULT	CASING DEPTH (m)	WATER LEVEL (m)	TYPE / DEPTH (m)	RESULT	FROM (m)	TO (m)	TYPE
	Stiff high to very high strength dark grey very gravelly CLAY. Gravel consists of fine to medium angular slag. (MADE GROUND)				▼					PP 3.00	PP=113			
										PP 3.50	PP=138	3.50		D
										PP 4.00	PP=142			
										PP 4.50	PP=125	4.50		D
	BOREHOLE TERMINATED AT 5.00m	5.00	289.59											

Key

D Small Disturbed Sample
B Bulk Disturbed Sample
ES Environmental Sample
W Water Sample
C Core sample
UT Undisturbed Sample

S Standard Penetration Test
C Standard Penetration Test (solid cone)

PP Pocket Penetrometer test
SV Shear Vane test
PID Photo Ionisation Detector test

Notes

Backfilled with arisings.

Groundwater observations

Groundwater encountered at 3m depth. Water level remained constant.

Title

Driven tube sampler record

Recovery details	
Range (m)	Recovery (%)
0.00 - 1.00	100
1.00 - 2.00	40
2.00 - 3.00	70
3.00 - 4.00	100
4.00 - 5.00	100

Method Driven tube sampler	**Logged by** TO	**Date(s)** 29/01/2019
Level (m OD) 294.59	**Compiled by** SA	**Sheet number** Sheet 2 of 2
Co-ordinates 406458mE, 374338mN	**Checked by** SD	**DTS29**

Report ref: STQ4642M-G01 **Revision:** 0

Appendix F

Areas Susceptible to Groundwater Flooding (High Peak Borough)
DCC Level 1 SFRA: Map 5.6


Areas Susceptible to Ground Water Flooding in High Peak Borough
Drawing No : - SFRA 5.6
Key
Areas Susceptible to Groundwater Flooding
< 25%
>= 25% <50%
>= 50% <75%
>= 75%
Hadfield
Glossop
Chinley
Whaley Bridge
Chapel-en-le-Frith
Buxton
Hayfield
Edale
Castleton
Hope
Drawing No
SFRA 5.6
Areas Susceptible to Ground Water Flooding in High Peak Borough
Prepared By
AD
Checked By
JRB
Approved By
SM
Date Issued
15/02/2012
© Crown copyright and database rights [2012]. Ordnance Survey [100023251]. You are not permitted to copy, sub-licence, distribute or sell any of this data to third parties in any form.
Scale: 1:160000 at A4
N

Appendix G

Historic Flood Incidence by Source and Floodzones (High Peak Borough)
DCC Level 1 SFRA: Map 3.6

Historic Flood Incidence by Source and Floodzones in High Peak Borough

Drawing No : - SFRA 3.6



Drawing No	SFRA 3.6
Historic Flood Incidence by Source and Floodzones in High Peak Borough	
Prepared By	AD
Checked By	JRB
Approved By	SM
Date Issued	02/08/2012

Scale: 1:160000 at A4

N

K
L

Appendix H

Preliminary Drainage Layout

Barratt Homes drawing no. H8797-BAH-XX-XX-DR-CE-300001-P07

Warning to House Purchasers

Buyers are warned that this is a working drawing and the contents of this drawing may be subject to change during the build process. The layout, form, content, and dimensions specified are included for general guidance only. Finishes or features shown may alter in respect of individual properties. Whilst we make every effort to ensure our drawings are up to date there may from time to time be an unavoidable delay in updating these due to changes in regulations and/or re-planning. Purchasers are advised to check with Sales Adviser whether any alterations have been made to this drawing. The contents of this drawing do not constitute a contract, part of any contract or warranty unless specifically incorporated into the contract. They should not be relied upon for the purposes of entering into a contract to purchase any property.

ENGINEERING LAYOUT NOTES

1. All adoptable drainage works have been designed and are to be constructed in accordance with "Sewerage Sector Guidance Appendix C – Design and Construction Guide v2.1", and United Utilities Guidelines. Where specification conflicts, UU guidelines shall take precedence.
2. All clay pipe work shall be extra strength clayware to BS 295 and BS65 (SW only).
3. All precast concrete pipework shall be to Class 120 in accordance with BS59911-Part 1, BS EN 1916 and bear the BS kitemark.
4. All adoptable drainage to be bedded in Class S granular surround unless otherwise stated on the longsections.
5. All concrete manhole and soakaways rings, and concrete cover slabs to be manufactured to BS EN 1917 and BS5911:Part 3.
6. Rising mains to be black polyethylene pipes complying to BS EN 13244-2. Polyethylene fittings, including fusion joints, and electro-fusion fittnigs shall comply with BS EN 13244-2.
7. All levels relate to Ordnance Datum. Contractor to ensure that this drawing is read in conjunction with the site specific topographical survey provided by Barratt Manchester and the benchmark information provided.
8. This drawing is to be read in accordance with all other relevant drawings.
9. The contractor shall be responsible for ensuring that any existing invert levels indicated on the drawings are correct before work commences.
10. All proposed connections to the sewer shall be 150ø unless stated otherwise.
11. All private house drainage shall be 100ø and all drag-out connections shall be 150ø at a minimum gradient of 1:80 unless otherwise stated; and laid in accordance with Part H of the Building Regulations.
12. Runoff from private surfaces shall not discharge across the highway. Gullies or channels shall be provided as appropriate to prevent this.
13. Pram crossings shall be provided at the inner tangent points of all junctions.
14. Pipes shall be protected from concentrated loading by construction traffic during the construction period when insufficient cover to the pipe may make them vulnerable to damage.
15. Insitu CBR tests of the road formation levels are to be carried out to determine the depth of pavement construction required. This is to be approved by Derbyshire County Council prior to construction of the road pavements.
16. Groundworker to ensure that plot drainage be within the curtilage of the plot they serve where possible and inspection covers kept within hardstanding where possible.
17. Contractor to provide Severn Trent Water with sufficient notice prior to commencement of sewer works on their Inspections telephone number.
18. Contractor to obtain all necessary highway opening notices from Derbyshire County Council, obtain approval to work on United Utilities Sewerage System, obtain approval to method statement from the Environment Agency and/or the Local Lead Flood Authority for any works affecting a watercourse.

ENGINEERING KEY

- S1 — S104 Adoptable Surface Water Sewer & Manhole
- (10.25) — Private Surface Water Drag-Out and Invert
- S1 — S38 Adoptable Surface Water Sewer & Manhole
- S38 Adoptable Road Gully
- F1 — S104 Adoptable Foul Water Sewer & Manhole
- 10.25 — Private Foul Drag-Out and Invert
- Proposed Adoptable Foul Water Rising Main
- Proposed S104 Sewer Easement
- PS1 — Proposed Adoptable Foul Water Pumpstation

Revision	Description	Date	Design By
P07	Updated design to suit planning layout revision Rev 3	01.07.24	CD
P06	Updated design to suit planning layout revision Rev 2	27.06.24	CD
P05	Reverted to pumped solution for the whole site.	14.02.24	BJM
P04	Updated design to suit planning layout revision N.	09.02.24	BJM

Project: Hogshaw Farm, Buxton

Description: Preliminary Drainage Layout

Design By:	Date:	Scale at A0:	Revision:
CD	Feb 2024	1:500	P07

Project	Originator	Functional	Spatial	Form	Discipline	Number
H8797	BAH	XX	XX	DR	CE	300001

BARRATT HOMES

Do not scale from this drawing. Work to given dimensions only. Any discrepancies are to be reported to Originator.

Appendix I
Greenfield Calculations

ICP SUDS Mean Annual Flood

Input

Return Period (years)	100	Soil	0.500
Area (ha)	3.720	Urban	0.000
SAAR (mm)	1374	Region Number	Region 4

Results l/s

QBAR Rural	45.2
QBAR Urban	45.2
Q100 years	116.2
Q1 year	37.5
Q30 years	88.6
Q100 years	116.2

Appendix J

Drained Area Plan

JPP Consulting drawing no. 11024-FRA05B

General notes

All dimensions are in metres unless otherwise stated.

All levels are in metres.

This drawing is to be read in conjunction with all relevant Engineers and Architect's drawings, Specifications, Reports and Engineering Details.

Do not scale from this drawing.

Based on Topographical Land Survey by SurveyEng Ltd, drawing number BH.TS.12 Rev C dated 26.03.2021.

Based on Planning Layout by Barratt Homes, drawing number H8797-BAH-XX-XX-DR-UD-203001-P03 dated 28.06.2024.

Drawing Key

Plot Areas = 5,665m^2

Driveway Areas = 3,904m^2

Road Areas = 9,260m^2

Total Area = 18,829m^2

10% Urban Creep to Plots = 567m^2

Total Drained Area including 10% Urban Creep = 19,396m^2

Site Boundary



Drawing is not to be used for construction until status is CONSTRUCTION

Rev B	Updated to suit latest site layout	By JPB	Checked	KER	12.07.2024
Rev A	Updated to suit latest site layout	By NCR	Checked	KER	31.01.2024

jpp

- Infrastructure Design
- Structural Engineering
- Development Planning
- Professional Advice
- Geotechnical & Environmental
- Surveying

Northampton
Grand Union Works, Whilton Locks, Daventry
Northamptonshire, NN11 2NH
T: 01604 781811

Poole & Milton Keynes

E: mail@jppuk.net **W**: jppuk.net

Client	Barratt Homes
Project	Proposed Residential Develolpment Land at Hogshaw Farm, Nunsfield Road, Buxton
Title	Drained Area Plan

Scale at A2	Drawn by	Checked by	Date
1:1000	IH	KER	26.04.2023

Status	Project ref	Drawing no.	Revision
FOR PLANNING	11024	FRA05	B

Appendix K
Attenuation Calculations

Summary of Results for 100 year Return Period (+40%)

Storm Event	Max Level (m)	Max Depth (m)	Max Control (l/s)	Max Volume (m³)	Status
15 min Summer	98.525	0.525	45.1	568.6	O K
30 min Summer	98.627	0.627	45.1	680.2	O K
60 min Summer	98.736	0.736	45.1	797.8	O K
120 min Summer	98.831	0.831	45.1	900.9	O K
180 min Summer	98.863	0.863	45.1	935.1	O K
240 min Summer	98.878	0.878	45.1	952.0	O K
360 min Summer	98.888	0.888	45.1	962.5	O K
480 min Summer	98.881	0.881	45.1	955.4	O K
600 min Summer	98.866	0.866	45.1	938.4	O K
720 min Summer	98.845	0.845	45.1	915.8	O K
960 min Summer	98.790	0.790	45.1	856.5	O K
1440 min Summer	98.662	0.662	45.1	717.6	O K
2160 min Summer	98.502	0.502	45.1	544.2	O K
2880 min Summer	98.390	0.390	45.0	422.3	O K
4320 min Summer	98.270	0.270	42.7	292.4	O K
5760 min Summer	98.232	0.232	35.9	252.0	O K
7200 min Summer	98.209	0.209	31.0	226.8	O K
8640 min Summer	98.192	0.192	27.3	208.4	O K
10080 min Summer	98.179	0.179	24.5	194.4	O K
15 min Winter	98.590	0.590	45.1	639.5	O K
30 min Winter	98.708	0.708	45.1	767.3	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
15 min Summer	164.198	0.0	582.3	18
30 min Summer	100.796	0.0	717.7	33
60 min Summer	61.875	0.0	892.8	62
120 min Summer	37.983	0.0	1097.5	120
180 min Summer	28.551	0.0	1238.2	166
240 min Summer	23.316	0.0	1348.8	196
360 min Summer	17.526	0.0	1521.4	260
480 min Summer	14.313	0.0	1657.1	330
600 min Summer	12.232	0.0	1770.5	400
720 min Summer	10.759	0.0	1868.9	470
960 min Summer	8.754	0.0	2027.5	608
1440 min Summer	6.545	0.0	2273.0	866
2160 min Summer	4.894	0.0	2558.3	1228
2880 min Summer	3.982	0.0	2774.5	1560
4320 min Summer	2.943	0.0	3070.9	2208
5760 min Summer	2.374	0.0	3313.1	2944
7200 min Summer	2.010	0.0	3505.4	3672
8640 min Summer	1.755	0.0	3669.9	4408
10080 min Summer	1.564	0.0	3811.9	5136
15 min Winter	164.198	0.0	653.7	18
30 min Winter	100.796	0.0	805.3	32